

To: 1020479 7-24  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-12920167-00-01 190R  
API NUMBER 15- Docket #E-23,598  
NW SE, SEC. 6, T. 33 S, R. 40 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

1980 feet from S section line  
1980 feet from E section line  
Lease Name Santa Fe Trail Unit A, 2-1  
County Morton  
Well Total Depth 5988 194.61 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1606  
Input Well  SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 2:30 p.m. Day: 22 Month: 7 Year: 19 92

Plugging proposal received from Don Horton  
(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 5546' w/500 sx cement, PBTD 5410', Perfs at 5354-5378'  
1st plug set CIBP at 5300', run 10 sx cement on top of CIBP with tubing,  
2nd plug pump 50 sx cement at 1656',  
3rd plug pump 50 sx cement at 800',  
4th plug pump 15 sx cement at 50-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 24 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5300', run 10 sx cement on top of CIBP with tubing,  
2nd plug pump 50 sx cement at 1656',  
3rd plug pump 50 sx cement at 800',  
4th plug pump 15 sx cement at 50-0'.  
Heavy mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2012' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)  
I (did / did not) observe this plugging.

INVOICED  
DATE 8-6-92  
INV. NO. 35871  
7-24

RECEIVED STATE CORPORATION COMMISSION JUL 29 1992  
SIGNED Glenn R Barlow (TECHNICIAN)  
CONSERVATION DIVISION WICHITA, KANSAS