

To: 1 100166
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

10-16

API NUMBER 15-129-20,337-0000
NW NW, SEC. 9, T. 33 S, R. 40 W/EX
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Goddard "A" Well # 1

Operator: Anadarko Petroleum Corporation
Name &
Address P.O. Box 351
Liberal, KS 67905-0351

County Morton 185.25

Well Total Depth 5700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1525

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 14 Month: 10 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Logs: 4 1/2" at 5699' w/900 sx cement, Perfs at 5476-94, 5509-20', DV @ 2896' w/600 sx cement
PBTD 5699'

1st plug pump 2 sx hulls and 20 sx cement on bottom.

2nd plug pump 20 sx cement at 2896',

3rd plug pump 60 sx cement at 1550',

4th plug pump 50 sx cement at 550', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Scott Alberg
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11 a.m. Day: 16 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug spotted 20 sx cement with 100 lbs. hulls from 5476-5276'.

Tagged plug at 5190'.

10/15/97 2nd plug ran tubing in hole to 2946' and spotted 20 sx cement from 2946-2746', tubing.

3rd plug cut off at 1796', pulled casing to 1550', pumped 60 sx cement,

4th plug pulled to 550' and pumped 50 sx cement,

5th plug on 10/16 topped off with 10 sx cement at 40'.

Remarks: Used common cement by Sargent & Horton. Recovered 1796' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE OCT 22 1997

INV. NO. 49235

Signed Gary Winters
(TECHNICIAN)

10-16 JAN 09 1998