

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20472-00-01  
Spot: SENE Sec/Twnshp/Rge: 5-34S-13W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: HOLMES H Well Number: 1  
County: BARBER Total Vertical Depth: 5094 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N. MARKET, SUITE 1000  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 5094 WITH 150 SX CMT  
Surface Casing Size: 8.625 feet: 457 WITH 350 SX CMT

\$165.56

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2003 9:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: ALAN DICK Company: WOOLSEY OPERATING Phone: (316) 267-4379

Proposed Plugging Method: CIBP @ 3750' & 2 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/22/2003 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4975'. PERFS AT 4984-4990, 4904-4914, 4875-4902'. SET CIBP @ 3750' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAY DOWN CASING. RUN 2 3/8" TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 40 SX CMT. 2ND PLUG AT 470' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
APR 29 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3313' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

*Stephen J. Puffer*  
(TECHNICIAN)

INVOICED  
DATE 4-29-03  
2003061470

Form CR-2/3