

1041329

TO: STATE CORPORATION COMMISSION

12-10

API NUMBER 15-007-22,567-0000  
SE SW SEC. 10, T 34 S, R 13 W  
NE

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME DONOVAN WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER 176.44

OPERATOR LICENSE # 5506 WELL TOTAL DEPTH 5429 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4770' WITH 100 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 10 3/4" @ 220' WITH 175 SX

ADDRESS MEDICINE LODGE, KS 67104

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 10 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 4634' TO 4638' NO WIPER PLUG-10 3/4" SWEDGED & WELDED BACK TO 8 5/8" AT SURFACE

CIBP AT 4600' AND 2 SX CEMENT. CUT AND LAY DOWN CASING. FROM SURFACE PUMP 300# HULLS-10 SX

GEL-50 SX CEMENT-10 SX GEL-100# HULLS-10 3/4" WIPER PLUG AND 125 SX CEMENT.

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 16 1998

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

CONSERVATION DIVISION  
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 10 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4600' AND PUT 2 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER.

2ND PLUG PUMP DOWN 10 3/4" SURFACE PIPE WITH 300# HULLS- 10 SX GEL- 50 SX CEMENT- 10 SX GEL-

100# HULLS-& 125 SX CEMENT. MAXIMUM PSI PRESSURE AT 350#. SHUT IN AT 0#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4000' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer  
(TECHNICIAN) FORM OP-2/3

DEC 17 1998  
60469

12-10

AUG 27 1999