

1 080467

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,109-0000

C W/2 NE, SEC. 10, T 34 S, R 13 W/E

3960 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Donovan "A" Well # 1

Operator: American Energies Corporation

County Barber 157.63

Name & Address 575 Fourth Financial Center

Well Total Depth 4850 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 522

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 10:00 am Day: 1 Month: January Year: 19 86

Plugging proposal received from M. Hogan

(company name) Wheatstate (phone) 316-672-7514
Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2068'-75'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

X

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 pm Day: 1 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2075' with 50 sx cement, 2nd plug at 550' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate
mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed) observe this plugging.

STATE CORPORATION COMMISSION

Signed

J. H. Metz
(TECHNICIAN)

DATE JAN 13 1986

JAN 6 1986

INV. NO. 11933

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84