

1 030784

FEB 2 1 1987

API NUMBER 15-119-20,754-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S/2 SW/4, SEC. 14, T 34 S, R 29 W/E
660 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9404

Lease Name Larrabee Well # 1-14

Operator: Rosewood Resources, Inc.
Name & Address: 200 Crescent Court, Suite 300
Dallas, TX 75201

County Meade 191.75
Well Total Depth 5900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1638

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Company, Inc. License Number 5421

Address 202 South St. Francis, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 21 Month: 2 Year: 19 87

Plugging proposal received from Preston Izzard

(company name) Sage Drilling Company, Inc. (phone) 316-263-6139

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2466'

1st plug at 4000' with 50 sx cement, 2nd plug at 1650' with 50 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 a.m. Day: 21 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 4000' with 50 sx cement,

2nd plug at 1650' with 50 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
FEB 25 1987
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (did not) observe this plugging.

DATE 2-26-87

Signed Steve Durrant (TECHNICIAN)

INV. NO. 16236

NOTICE OF INTENTION TO DRILL

Starting Date 02 04 87 (see rules on reverse side)

API Number 15- 119-20,754-0000

OPERATOR: License # 9404 Name Rosewood Resources, Inc. Address 200 Crescent Court, Suite 300 City/State/Zip Dallas, Texas 75201 Contact Person Gilbert Wolfe Phone 214/871-5700

C. S/2 SW/4 Sec. 14 Twp. 34 S, Rg. 29 XX West 660 Ft. from South Line of Section 3960 Ft. from East Line of Section

CONTRACTOR: License # 5421 Name Sage Drilling Co., Inc. City/State Wichita, Kansas

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 660 feet County Meade

Well Drilled For: Oil SWD Infield XX Mud Rotary XX Gas Inj XX Pool Ext. Air Rotary OWWO Expl Wildcat Cable

Lease Name Larrabee Well # 1-14 Ground surface elevation Est. ±2466 feet MSL Domestic well within 300 feet: yes XX no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Municipal well within one mile: yes XX no Depth to bottom of fresh water 2480 Depth to bottom of usable water 500

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 1-23-87 Signature of Operator or Agent Gilbert Wolfe Title Operations Specialist

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 500 feet per Alt. 1X This Authorization Expires 7-23-87 Approved By [Signature] 1-23-87

Set 1600' of 8 5/8 SPUD 2-10-87

C. S/2 SW Sec. 14 Twp. 34 S, Rg. 29 West

10:00 316-225-3055

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1500 30' of surface feet depth with 50 SXS of 60/40 jazz 6% gel 2nd plug @ 650 feet depth with 25 40 SXS of common 3rd plug @ 40-0 feet depth with 10 SXS of 4th plug @ feet depth with SXS of 5th plug @ feet depth with SXS of (2) Rathole with 10 SXS (b) Mousehole with 10 SXS

PUSHER Proctor 13320 TD 5900 FORMATION Miss SURFACE PIPE 8 5/8 @ 1638 ANHYDRITE ELEVATION 2466 STARTING TIME & DATE 4:00 AM COMPLETION TIME & DATE 8:00 AM 1st PLUG @ 4000' FT. W/ 50 SX 2nd PLUG @ 1650 FT. W/ 50 SX 3rd PLUG @ 650 FT. W/ 50 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ Pump former used 1-23 last bull. CEMENT COMPANY well - TECHNICIAN Hollibaugh 6/4 6:10 S.D. STATE CORPORATION COMMISSION FEB 23 1987 CONSERVATION DIVISION Wichita, Kansas