

To: ¹ 020632 12-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,543-0000 106 p

NE SW, SEC. 35, T 34 S, R 35 WEX

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Rennick Well # A-2

Operator: OXY USA INC.

County Stevens

Name & Address P.O. Box 26100

Well Total Depth 6700 217.75 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1656

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address P.O. Box 1383, Guymon, OK 73942-1383

Company to plug at: Hour: 12:30 p.m. Day: 22 Month: 12 Year: 19 92

Plugging proposal received from Tom Patten

(company name) OXY USA INC. (phone) 316-675-2293

were: 5 1/2" at 6693' w/200 sx cement, TOC 6000', PBD 6619', Perfs at 6480-93'

1st plug set CIBP at 6400' and dump .2 sx cement on top,

2nd plug pull 5 1/2" and run tubing to 2677', pump 80 sx cement,

3rd plug pump 50' sx cement at 1674',

4th plug pump 40 sx cement at 718', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 23 Month: 12 Year: 1992

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6410' and dump 2 sx cement on top with bailer,

2nd plug pulled 5 1/2"; ran tubing to 2677', pumped 80 sx cement,

3rd plug pumped 50 sx cement at 1674',

4th plug pumped 40 sx cement at 718',

5th plug pumped 10 sx cement at 40 to -4'. All plugs displaced with mud.

Remarks: Used common cement by Gibson's. Recovered 2677' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 1-14-93

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 37204

12-23

RECEIVED
COMMISSION
DEC 30 1992
CONSERVATION DIVISION
KANSAS