

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

11-7  
RECEIVED  
STATE CORPORATION COMMISSION  
11-13-90  
NOV 13 1990  
CONSERVATION DIVISION  
Wichita, Kansas

2-040580

API NUMBER: 15-072-20,768-0000 <sup>077</sup>

NE SE SE , SECTION 2 TOWNSHIP 34 RANGE 9W

OPERATOR LICENSE # 5038 990 FEET FROM S SECTION LINE  
330 FEET FROM E SECTION LINE

OPERATOR Robinson Oil Company  
NAME & 300 West Douglas, #420  
ADDRESS Wichita, KS 67202

LEASE NAME: Martin #C-1  
COUNTY: Harper

WELL TOTAL DEPTH: 4941' <sup>160.58</sup>

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 248'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Bobby Hoover  
COMPANY NAME: Kelso Casing Pulling PHONE: \_\_\_\_\_

WERE: 5-1/2" @ 4548' - perfs 4594-4604' - PBTD 4778' - 30 sx  
@ 1000' - 30 sx @ 700' - circ 300' - rec. 3320'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 13:00 DAY: 7 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Perfs were sanded to 4350' & capped w/5 sx cmt - 5-  
1/2" recovered from 3320' and pulled to 1000' where 30  
sx cmt spotted - 5-1/2" pulled to 700' where 30 sx cmt  
spotted - 5-1/2" pulled to 300' and cmt circ to  
surface.

REMARKS: B. J. Services #636305 40/60 2% gel

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson  
Steve Van Gieson (AGENT)

INVOICED

DATE 11-19-90  
NO. 29995