

1 020043

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-20,939-0000  
C NE SW, SEC. 34, T 34 S, R 35 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Parsley B Well # 2

Operator: Cities Service Oil & Gas Corporation  
Name & Address 3545 NW 58th Street  
Oklahoma City, OK 73112

County Stevens 222.63  
Well Total Depth 6850 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1677

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Exeter Drilling Company License Number 3098

Address Denver, Colorado

Company to plug at: Hour: 6 p.m. Day: 9 Month: 12 Year: 19 86

Plugging proposal received from Steve Milinichik  
(company name) Cities Service Oil & Gas Corporation (phone) 316-675-2293

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 4300' with 50 sx cement, 2nd plug at 3300-2600' with 150 sx cement,  
3rd plug at 1730' with 50 sx cement, 4th plug at 700' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 a.m. Day: 10 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 4306' with 50 sx cement,

2nd plug at 3300' with 150 sx cement,  
3rd plug at 1730' with 50 sx cement,  
4th plug at 700' with 40 sx cement,  
5th plug at 0-40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION  
DEC 10 1986  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 65/35 Pozmix Class H cement by Dowell.

(If additional description is necessary, use BACK of this form.)

**INVOICED** (10/20/86) observe this plugging.

DATE 12-16-86

Signed Glenn R Barber  
(TECHNICIAN)

INV. NO. 1564