

To: 1 060076  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

11-11

API NUMBER 15- 189-20,672-~~0001~~  
S/2 NW SE, SEC. 33, T 34 S, R 35 W/X  
1650 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Koch B Well # 1  
County Stevens 219.38

Operator: OXY USA Inc.  
Name:  
Address P.O. Box 300  
Tulsa, OK 74102-0300

Well Total Depth 6750 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1682

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gibson Well Service License Number 5866

Address Ulysses, KS

Company to plug at: Hour: 9:00 a.m. Day: 10 Month: 11 Year: 19 97

Plugging proposal received from Reid Wilson

(company name) Halliburton Services (phone) 316-629-3578

were: 5 1/2" at 6730' w/175 sx cement, CIBP at 6465', Perfs at 6257-68', PBSD 6455'  
1st plug set CIBP at 6200' with 2 sx cement on top,

2nd plug spot 100 sx cement over Council Grove, 3rd plug at 1735' with 50 sx cement,

4th plug at 600' with 40 sx cement,

5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Mike Maier  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:20 p.m. Day: 11 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6220' with 2 sx cement on top, 2nd plug perforated at 3000' and spotted 125 sx cement and 300 lbs. hulls, displaced with gel,  
KANSAS CORPORATION COMMISSION

3rd plug spotted 50 sx cement at 1736-1520', displaced with gel,

4th plug spotted 40 sx cement at 621', displaced with gel,

NOV 19 1997

5th plug at 45-0' with 10 sx cement. CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used HLC with 3% cc cement by Halliburton. Recovered 1756' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXX/ did not) observe this plugging.

DATE NOV 24 1997

Signed Michael Maier  
(TECHNICIAN)

INV. NO. 49571

JAN 29 1998