

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22421-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 30-34S-35W
1126 feet from S Section Line, 1369 feet from W Section Line
Lease/Unit Name: WILLIAMS F Well Number: 1
County: STEVENS Total Vertical Depth: 6822 feet

Operator License No.: 5447

Conductor Pipe: Size feet: 8.221.72

Op Name: OXY USA, INC.

Surface Casing: Size 8.625 feet: 1745 WITH 750 SX CMT

Address: PO BOX 27570 5 E GREENWAY PLZ STE
HOUSTON, TX 77227

Production: Size 4.5 feet: 6560 WITH 250 SX CMT

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/16/2002 1:30 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 20 SX CMT & 100# HULLS TO BOTTOM. 1ST PLUG AT 3200' WITH 100 SX CMT. 2ND PLUG AT 1780' WITH 50 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 09/17/2002 3:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 6426'. PERFS AT 6281-91'. PUMPED 100# HULLS & 20 SX CMT. 1ST PLUG PULLED CASING TO 3200'. LOADED HOLE WITH MUD & CIRCULATED. PUMPED 100 SX CMT. 2ND PLUG PULLED TO 1780'. 09/17/02: PUMPED 50 SX CMT. 3RD PLUG PULLED TO 800' & PUMPED 40 SX CMT. 4TH PLUG PULLED TO 40' & PUMPED 10 SX CMT.

RECEIVED

SEP 23 2002

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 3330' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED SEP 18 2002

DATE

9-24-02 MP

INV. NO.

2003060544

[Signature]
Part 2/3