

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22393-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 28-34S-35W
878 feet from S Section Line, 772 feet from W Section Line
Lease/Unit Name: WONDER C Well Number: 4
County: STEVENS Total Vertical Depth: 6875 feet

Operator License No.: 5447

Conductor Pipe: Size feet:

Op Name: OXY USA, INC.

Surface Casing: Size 8.625 feet: 1743

Address: PO BOX 27570 5 E GREENWAY PLZ STE
HOUSTON, TX 77227

Production: Size feet:

Liner: Size feet:

\$ 223.44

Well Type: DH

UIC Docket No:

Date/Time to Plug: 07/18/2001 5:05 PM

Plug Co. License No.: 5929

Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: JAKE

Company: OXY USA

Phone: (713) 215-7312

Proposed Plugging Method: 1ST PLUG AT 3000' WITH 100 SX CMT. 2ND PLUG AT 1750' WITH 50 SX CMT. 3RD PLUG AT 740' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 07/18/2001 9:05 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

1ST PLUG AT 3000' WITH 100 SX CMT. 2ND PLUG AT 1750' WITH 50 SX CMT. 3RD PLUG AT 740' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2001

CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

INVOICED

Plugged through: DP

DATE 8-3-01

NO. 2002060171

District: 01

Signed Jim Holland PART II
(TECHNICIAN)

JUL 19 2001

MP

Form CB-213