

12-14

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-21 274-00-00
C SE NW, SECTION 23 TOWNSHIP 34 RANGE 9W

OPERATOR LICENSE # 31355

3300 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE
RECEIVED
KANSAS CORPORATION COMMISSION

OPERATOR W C PAYNE
NAME & 800 UNITED FOUNDERS TOWER
ADDRESS OKLAHOMA CITY OK 73112

FEB 09 1994

LEASE NAME: JUDY #1
COUNTY: HARPER
WELL TOTAL DEPTH: 4995'
CONSERVATION DIVISION
WICHITA, KS

CONDUCTOR PIPE: 162.34

SURFACE CASING: 8-5/8" @ 305'

ABANDONED OIL WELL GAS WELL INPUT WELL S&W D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: EAGLE DRILLING INC
ADDRESS: WICHITA KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: BUTCH STEINERT

COMPANY NAME: EAGLE DRILLING INC PHONE: _____

WERE: 35 SX @ 1450' - 35 SX @ 950' - 35 SX @ 360' - 25 SX @ 60' - 15 SX RAT - 10 SX MOUSE

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1930 DAY: 14 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:

DRILL PIPE RUN OPEN END TO 1450' & 35 SX CMT SPOTTED
- DRL PIPE PULLED TO 950' - 35 SX SPOTTED - DRL PIPE
PULLED TO 360' & 35 SX CMT SPOTTED - DRL PIPE PULLED TO
60' & CMT CIRC TO SURF - RAT HOLE CIRC W/15 SX & MOUSE
HOLE CIRC W/10 SX CMT

REMARKS: HALLIBURTON 60/40 4%

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

/s/
Steve Van Gieson (AGENT)

DATE 2-9-94
INV. NO. 39905