

1050304

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,826 - 0000

C SW NW SEC. 35 T 34 S. R. 21 W X  
SE Corner of  
3300 feet from NXS section line  
4620 feet W from NXS SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Barby-Harper Well # 'H' 1

Operator: Donald C. Slawson  
Name & Address 200 Douglas Building  
Wichita, KS 67202

County Clark

Well Total Depth 5725 186.06 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 820

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 6:00 am Day: 3 Month: August Year: 1984

Plugging proposal received from Ron Rowe

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 870' with 50 sx cement

2nd plug at 420' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:30 am Day: 3 Month: August Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement, 2nd plug at 420' with 40  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with  
10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 07 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form)

(copy / copy not) observe this plugging.

INVOICED

DATE 8-17-84

INV. NO. 3231

Signed Richard W. Lacey (TECHNICIAN)

8-3 . SEP 11 1984