

To: 1 051867 11-18
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-21,087-0000
NE SE SW, SEC. 35, T 34 S, R 21 W/R
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5003
Operator: McCoy Petroleum Corp.
Name & Address: 3017 N. Cypress
Wichita, KS 67226-4003

Lease Name Barby B Well # 1-35
County Clark 186.06
Well Total Depth 5725 feet
Conductor Pipe: Size 20" feet 50
Surface Casing: Size 8 5/8" feet 612

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Shawnee Well Service License Number 30346
Address P.O. Box 781624, Wichita, KS 67278-1624

Company to plug at: Hour: 10 a.m. Day: 18 Month: 11 Year: 19 94

Plugging proposal received from Daryl Hanson
(company name) McCoy Petroleum Corp. (phone) 316-272-1296

were: 4 1/2" at 5725' w/150 sx cement, PBDT 5676', Perfs at 5552-5555'
1st plug set CIBP at 50' above perfs at 5500' with 2 sx cement on top,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11 a.m. Day: 18 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5500' with 2 sx cement on top,
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3618' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 12-6-94
INV. NO. 41802
11-18

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
NOV 22 1994
11-22-94
STATE CORP COM