

To: 1 061080
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5654

Operator: Rine Drilling Company
Name & Address: 300 West Douglas, Suite 600
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Drawer 1431, Duncan, OK 73536

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 3 Year: 19 88

Plugging proposal received from Jerry Young

(company name) Rine Drilling Company (phone) 316-635-2508

were: 4 1/2" at 4441' Perfs at 900-1100' Backside cemented to surface from 1250' w/400 sx cement

1st plug set CIBP above producing zone with 4 sx cement on top,

2nd plug set CIBP at 1250',

3rd plug pump 1 sx hulls and 150 sx cement filling 4 1/2" to 0',

4th plug pump into 8 5/8" with 50" sx cement if it will take it.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 23 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP above producing zone with 4 sx cement,

2nd plug set CIBP at 1250',

3rd plug pumped 1 sx hulls and 150 sx cement, filling 4 1/2" to 0',

4th plug pumped into 8 5/8" with 1/2 barrel of water, locked up at 300 lbs.

Maximum pressure 300 psi and shut in 300 psi.

Remarks: Used Class H cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 3-29-88

INV. NO. 20255

3-23-88 15-025-20551-0000
15-025-20551-00.00
API NUMBER 15- Docket #D-21,652

NW NW NE, SEC. 27, T 34 S, R 21 W/2

4950 feet from S section line

2310 feet from E section line

Lease Name Barby Well # 3-27

County Clark 142.35

Well Total Depth 4380 feet

Conductor Pipe: Size 20" feet 105'

Surface Casing: Size 8 5/8 feet 866

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1988

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi (TECHNICIAN)