

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20477-00-00  
Spot: CNWNWNW Sec/Twnshp/Rge: 27-34S-21W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease/Unit Name: BARBY Well Number: 1-27  
County: CLARK Total Vertical Depth: 4415 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N. TYLER  
WICHITA, KS 67212

Conductor Pipe: Size 20 feet: 80 \$143.49  
Surface Casing: Size 8.625 feet: 868 WITH 500 SX CMT  
Production: Size 4.5 feet: 4413 WITH 175 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/16/2002 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4275 WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/16/2002 10:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4371'. PERFS AT 4318-4348'. CIBP @ 4275' WITH 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 500#.

RECEIVED  
AUG 20 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3100' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed 

(TECHNICIAN)

INVOICED

AUG 16 2002

DATE 8-21-02

INV. NO. 2003060302 

FORM 01-2/3 