

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20542-00-00  
Spot: CNWNENW Sec/Twnshp/Rge: 27-34S-21W  
330 feet from N Section Line, 916 feet from W Section Line  
Lease/Unit Name: BARBY Well Number: 2-27  
County: CLARK Total Vertical Depth: 4481 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N. TYLER  
WICHITA, KS 67212

Conductor Pipe: Size 20 feet: 154 **445.63**  
Surface Casing: Size 8.625 feet: 849 WITH 600 SX CMT  
Production: Size 4.5 feet: 4478 WITH 175 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/16/2002 10:35 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4275' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/16/2002 11:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4449'. PERFS AT 4323-26'. CIBP @ 4275' WITH 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 500#.

RECEIVED

AUG 20 2002

8-20-02

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3100' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed: 

(TECHNICIAN)

INVOICED

AUG 16 2002

DATE

8-21-02

INV. NO.

2003060302

Form SP-2/3 