

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20544-00-00
Spot: NENENE Sec/Twnshp/Rge: 27-34S-21W
4950 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: BARBY Well Number: 4-27
County: CLARK Total Vertical Depth: 5618 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

Production Casing Size: 5.5 feet: 5575 WITH 400 SX CMT
Surface Casing Size: 8.625 feet: 856 WITH 600 SX CMT⁵⁹
#182

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2003 10:55 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BROADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4250' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2003 11:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4910'. PERFS AT 4298-4303'. CIBP @ 4910'. SAND TO 4250' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 400#.

RECEIVED
SEP 10 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3070' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 9-10-03

INV. NO. 2004060489