

1 090170

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,787-0000
NE NE SW, SEC. 24, T 34 S, R. 21 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from ~~N/S~~ section line
2310 feet from ~~W/E~~ section line

Operator License # 7744

Lease Name Barby-Harper Well # 1-24

Operator: Sho-Bar Energy, Inc.

County Clark

Name & Address Box 217

Well Total Depth 5540 180.05 feet

Harper, KS 67058

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 871

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&X _____

Other well as hereinafter indicated _____

Plugging Contractor DaMac Drilling, Inc. #1 License Number 6333

Address Box 1164, 624 Washington, Great Bend, KS 67530

Company to plug at: Hour: 4:00 am Day: 25 Month: May Year: 19 84

Plugging proposal received from Allen Barby

(company name) DaMac (phone) 316-692-1353

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 930' with 50 sx cement
solid bridge

2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement

4th plug to circulate rat hole with 15 sx cement

5th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by R. Bearlutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 am Day: 25 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement, 2nd & 3rd plugs - solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to circulate rat hole with 15 sx cement, 5th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 01 1984

6-1-84

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied # 34465
(If additional description is necessary, use BACK of this form)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (copy / bill not) observe this plugging.

Signed R. Bearlutton
(TECHNICIAN)

DATE 6-6-84

INV. NO. 1906 JUN 08 1984
5-23