

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20569-00-00
Spot: CSWSWSW Sec/Twnshp/Rge: 23-34S-21W
330 feet from S Section Line, 330 feet from W Section Line
Lease/Unit Name: BARBY Well Number: 1-23
County: CLARK Total Vertical Depth: 4448 feet

Operator License No.: 5055
Operator Name: TODD, C.H. INC.
Address: 100 S. MAIN, STE 415
WICHITA, KS 67202

Conductor Pipe: Size 20 feet: 80
Surface Casing: Size 8.625 feet: 844 WITH 500 SX CMT
Production: Size 4.5 feet: 4443 WITH 175 SX CMT
Liner: Size feet: 14456

Well Type: SWD UIC Docket No: D22000.0 Date/Time to Plug: 11/07/2000 10:00 AM

Plug Co. License No.: 6547 Plug Co. Name: SARGENTS CASING PULLING SERVICE

Proposal Revd. from: KIRBY LILLARD Company: SARGENTS CASING PULLING SER Phone: (316) 624-7455

Proposed Plugging Method: SET CIBP @ 4100'. 1ST PLUG AT 880' WITH 50 SX CMT. 2ND PLUG AT 440' WITH 25 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/07/2000 12:15 PM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 4100' WITH 2 SX CMT ON TOP. TESTED CASING FROM 0 TO 4100'. HELD AT 800 PSI. 1ST PLUG PULLED CASING TO 879'. LOAD HOLE WITH MUD AND SPOT 50 SX CMT. 2ND PLUG PULL TO 460' AND SPOT 25 SX CMT. 3RD PLUG PULL TO 40' AND SPOT 10 SX CMT. STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 2000
11-9-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 3040' OF 4 1/2' CASING.

Plugged through: CSG

District: 01

INVOICED

Signed

(TECHNICIAN)

DATE

11/9/00

INV. NO

2001060952

NOV 08 2000

Form CR-28