

1 030801

5-19-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,980-0000  
SW SW NE, SEC. 22, T 34 S, R 23 (W/E)  
2970 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9657

Operator: Quintana Petroleum Corporation  
Name & Address 1050-17th Street, Suite 400  
Denver, CO 80265

Lease Name Dunne Ranch Well # 1-22  
County Clark 35.00  
Well Total Depth 811 feet  
Conductor Pipe: Size 20" feet 89  
Surface Casing: Size \_\_\_\_\_ feet

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Brandt Drilling Company, Inc. License Number 5840

Address 105 South Broadway, Suite 920, Wichita, KS 67202

Company to plug at: Hour: 12 a.m. Day: 12 Month: 5 Year: 19 87

Plugging proposal received from Bob Moorehead

(company name) Quintana Petroleum Corporation (phone) 303-628-9211

were: to fill hole with heavy mud and spot cement through drill pipe LOST HOLE

1st plug pump 50 sx cement at 310',

2nd plug pump 30 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 a.m. Day: 19 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 310' with hulls and 50 sx cement-ran wire line to 471'-  
no cement in hole,

2nd plug at 310' with 30 sx cement and 1 sx hulls, (used 50/50 Pozmix 6% gel 2% cc on 1st & 2nd)

3rd plug pumped 140 sx light cement with 2% cc,

4th plug tagged cement at 64' and filled hole with 5 yards cement (ready mix). Paul Luthi

5-22-87 MAY 22 1987 witnessed.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita Kansas

Remarks: Used 50/50 Pozmix 6% gel 2% cc and light cement with 2% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Steve Durrant  
(TECHNICIAN)

DATE 5-27-87

INV. NO. 17000

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 4, 1987

API Number 15-025-20,980-0000

OPERATOR: License # 9657
Name: QUINTANA PETROLEUM CORPORATION
Address: 1050-17th St., Suite 400
City/State/Zip: Denver, Colorado 80265
Contact Person: E. Scott Kimbrough
Phone: (303)628-9211

.SW .SW .NE Sec. 22 Twp. 34S S, Rg. 23
2970' Ft. from South Line of Section
2310' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 2310 feet
County: Clark

CONTRACTOR: License # 5840
Name: BRANDT DRILLING Co. Inc.
City/State: Wichita, Kansas

Lease Name: DUNNE RANCH Well #: 11-22
Ground surface elevation 1867 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Inj X Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

If OWWO: old well info as follows:
Operator:
Well Name:
Comp Date: Old Total Depth:

Depth to bottom of fresh water 100'
Depth to bottom of usable water 200'

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 800'

Conductor pipe required N/A
Projected Total Depth 5620' feet

Formation: Chester

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date: 4/23/87 Signature of Operator or Agent Title: Production Technician

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. 1 & 2
This Authorization Expires 10-24-87 Approved By 4-24-87

Spud 5-11-87 10:00 AM
800' 8 1/8"
water well

.SW .SW .NE Sec. 22 Twp. 34S S, Rg. 23
East
West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 400'-200' feet depth with 50 sxs of 60/40 Poz w/6% gel
2nd plug @ 50' to surface feet depth with 10 sxs of 60/40 Poz w/6% gel
3rd plug @ feet depth with sxs of
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 10 sxs (b) Mousehole with 10 sxs

Table with columns: PUSHER, TD, SURFACE PIPE @, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1987
CONSERVATION DIVISION
Wichita, Kansas