

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21298-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 34-28S-12W  
660 feet from S Section Line, 676 feet from W Section Line  
Lease/Unit Name: EUBANK Well Number: A-1  
County: PRATT Total Vertical Depth: 4445 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

Production Casing Size: 4.5 feet: 4444 WITH 150 SX CMT  
Surface Casing Size: 8.625 feet: 414 WITH 275 SX CMT  
*14440*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2003 2:15 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: SAND TO 4200' & 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/22/2003 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PERFS AT 4257-4267'. SANDED BACK TO 4200' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 100#.

RECEIVED  
OCT 14 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1902' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Puffer*

(TECHNICIAN)

INVOICED

10-14-03

INV. NO. 2004060609

Form C-23