

1 080154

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,309 - 00-00

~~NE~~ NE NW, SEC. 34, T 28 S, R 12 ~~W~~ ~~EX~~

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Konold-Lawton Well # 1

Operator: Patton Oil Company

County Pratt

Name & Address 5660 S. Syracuse Circle, Suite 200
Englewood, CO 80110

Well Total Depth 4600 149.50 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 409

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 29 Month: May Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4595' PBTD 4490' Perfs 4113-19' 4475-79'

1st plug pump 35 sx cement and stop plug at 4000'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by J. A. Meij
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 pm Day: 29 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4595' PBTD 4490' Perfs 4113-19' 4475-79'

1st plug pumped 35 sx cement and stopped plug at 4000', 2nd plug squeezed well with
3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber
plug and pumped an additional 125 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 2600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 6-8-84

Signed JUN 07 1984

INV. NO. 1935

CONSERVATION DIVISION
Wichita, Kansas

J. A. Meij
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84