

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20163-00-02

Spot: CS2SE

Sec/Twnshp/Rge: 32-34S-27W

730 feet from S Section Line, 1320 feet from E Section Line

Lease/Unit Name: THORNOFF

Well Number: 132

County: MEADE

Total Vertical Depth: 6250 feet

Operator License No.: 3795

Op Name: SOUTH FORTY, THE, INC.

Address: PO BOX 446

LAVERNE, OK 73848

Conductor Pipe: Size

feet:

203.13

Surface Casing: Size 8.625

feet: 850

Production: Size 4.5

feet: 6250

Liner: Size

feet:

Well Type: SWD

UIC Docket No: D26477.0

Date/Time to Plug: 05/14/2002 10:00 AM

Plug Co. License No.: 32833

Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.

Proposal Rcvd. from: ALLEN BARBY

Company:

Phone: (580) 921-3366

Proposed  
Plugging  
Method:

PUMP 20 SX CMT & 200# HULLS AT 5850'. 1ST PLUG AT 1220' WITH 50 SX CMT. 2ND PLUG AT 880' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 05/14/2002 3:00 PM

KCC Agent: KEVIN STRUBE

**Actual Plugging Report:**

PBTD 6050'. PERFS AT 5974-88'. PUMP 20 SX CMT & 200# HULLS FOR BOTTOM PLUG. 1ST PLUG AT 1220' WITH 50 SX CMT. 2ND PLUG AT 880' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

RECEIVED

JUN 05 2002

6-5-02

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SARGENT & LILLARD. RECOVERED 2720' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

MAY 22 2002

DATE

6-6-02

INV. NO.

2002061887

Form 052/3