

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20788-00-00
Spot: CW2NW Sec/Twnshp/Rge: 29-34S-27W
1320 feet from N Section Line, 600 feet from W Section Line
Lease/Unit Name: BARBY Well Number: 1
County: MEADE Total Vertical Depth: 3350 feet

Operator License No.: 32972
Op Name: THE SOUTH FORTY, INC.
Address: PO BOX 446
LAVERNE, OK 73848

Conductor Pipe: Size 16 feet: 40 \$108.88
Surface Casing: Size 8.625 feet: 921
Production: Size 4.5 feet: 3345
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/09/2002 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS AT 3000'. LOAD HOLE WITH MUD. 1ST PLUG AT 1220' WITH 40 SX CMT. 2ND PLUG AT 940' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/09/2002 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PERFS AT 3133-38, 3214-16, & 3220-24'. 5/08/02: PUMPED 200# HULLS WITH 20 SX CMT. SHOT 4 1/2" OFF AT 2040' & PULLED TO 1220'. 05/09/02: 1ST PLUG LOAD HOLE WITH MUD, PUMP 40 SX CMT AT 1220'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 4 1/2" TO 940' & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT TO SURFACE.

RECEIVED
MAY 24 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS & LILLARD. RECOVERED 2040' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 5-28-02

INV. NO. 2002061848

MAY 21 2002

Form CP-118