

1090971

TO: STATE CORPORATION COMMISSION 11-11

API NUMBER 15-119-20,811-0000
SE SW SW SEC. 20, T 34 S, R 27 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4291 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BARBY WELL # 2-20B

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 106.05

OPERATOR LICENSE # 3795 WELL TOTAL DEPTH 3263 FEET

OPERATOR: THE SOUTH FORTY, INC PRODUCTION CSG: SIZE 4 1/2" @ 3263' WITH 150 SX

NAME AND PO BOX 446 SURFACE CASING: SIZE 8 5/8" @ 818' WITH 510 SX

ADDRESS LAVERNE, OK 73848 CONDUCTOR CSG: SIZE 1 3/8" @ 160' WITH 165 SX

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CSG. PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 11 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KIRBY LILLARD

(COMPANY NAME) SARGENT AND HORTON PLUGGING (PHONE) 316-624-7455

WERE: PERFS AT 3008-3190

1ST PLUG PUMP 300# HULLS, 20 SX CEMENT TO 2900'. SPOT PLUG THROUGH CASING.

2ND PLUG AT 1350' WITH 50 SX CEMENT, 3RD PLUG AT 840' WITH 50 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 11 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMP 300# HULLS, 20 SX CEMENT TO 2900'. SPOT PLUGS THROUGH CASING

2ND PLUG AT 1350' WITH 50 SX CEMENT, 3RD PLUG AT 840' WITH 50 SX CEMENT,

4TH PLUG AT 40' WITH 10 SX CEMENT.

11-18-98

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2495' OF 4 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3

DEC 01 1998 60392

11-11 JAN 29 1999