

1051292

4-18-90

158
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,810-0000
App. C S/2
S/2 SW, SEC. 20, T. 34 S, R. 27 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3795

Lease Name Barby Well # 2-20-A

Operator: The South Forty, Inc.

County Meade 35.00

Name & Address RR #1, Box 118

Well Total Depth 572 feet

Laverne, OK 73848

Conductor Pipe: Size _____ feet

Surface Casing: Size 16" feet 30'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Diamond "D" Trucking, Inc. License Number 3760

Address P.O. Box 442, Laverne, OK 73848

Company to plug at: Hour: 8 a.m. Day: 18 Month: 4 Year: 19 90

Plugging proposal received from Allen Barby

(company name) The South Forty, Inc. (phone) 405-921-3366

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug pump 70 sx cement down 4 3/4" drill collars to 300',

2nd plug run 1" pipe to 140' and pump 50 sx cement,

3rd plug pull 1" to 60' and circulate cement to surface using 50 sx cement,

4th plug pump 15 sx cement in rathole.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 18 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 4 3/4" drill collars stuck from 300-0',

1st plug pumped 70 sx cement down 4 3/4" drill collars to 300',

2nd plug ran 1" pipe to 140' and pumped 50 sx cement,

3rd plug pulled 1" to 60' and circulated cement to surface using 50 sx cement,

4th plug pumped 15 sx cement in rathole.

RECEIVED

STATE CORPORATION COMMISSION
Remarks: Used 60/40 Pozmix 6% gel by Western.

APR 25 1990 (if additional description is necessary, use BACK of this form.)

4-23-90 observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 5-4-90

INV. NO. 28024