

To: 1 020417
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-24
API NUMBER 15- Drilled 1962 15-119-10301-000054

C SW, SEC. 14, 'T. 34 S, R 27 W/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9183
Operator: Bentley & Laing
Name &
Address P.O. Box 294
Wichita, Falls, TX 76307

Lease Name Geo. Merkle Well # 1
County Meade 199.55
Well Total Depth 6140 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 3 5/8 feet 1390

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547
Address P.O. Box 506, Liberal, KS 67905

Company to plug at: Hour: 1 p.m. Day: 22 Month: 10 Year: 19 91

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 6140' w/200 sx cement. Perfs at 6042-72'
1st plug pump 1 sx hulls and 25 sx cement over perfs,
2nd plug pump 50 sx cement at 1400',
3rd plug pump 40 sx cement at 400',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 24 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs,
2nd plug pumped 50 sx cement at 1420', hole loaded with mud,
3rd plug pumped 40 sx cement at 625', displaced with mud,
4th plug pumped 10 sx cement at 40 to -4'.

RECEIVED
OCT 30 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3024' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

do not observe this plugging.

INVOICED
DATE 11-13-91
INV. NO. 33693
10-24

Signed Glen R. Barlow
(TECHNICIAN)