

1060423

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SE NE _____, SEC. 9 _____, T 34 _____ S, R 27 _____ WXX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Not Available
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5461

Lease Name Merkle Well # 1-9

Operator: Horizon Oil & Gas Co.

County Meade 196.46

Name & Address P. O. Box 7

Well Total Depth 6045 feet

Spearman, TX 79081-0007

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1360

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sams Well Service License Number 6145

Address Box 67, Guymon, OK 73942

Company to plug at: Hour: 4:00 pm Day: 7 Month: December Year: 19 84

Plugging proposal received from Curtis Covington

(company name) Horizon (phone) 806-659-2544

were: 2 7/8" set at 6030' PBTD 6000' Perfs at 5943-5975'

1st plug set CIBP at 5893'

2nd plug at 2300' with 35 sx cement

3rd plug at 1400' with 40 sx cement

4th plug at 660' with 30 sx cement

solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Paula A. Luthis (TECHNICIAN)
cement to surface with 10 sx cement

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 5:30 pm Day: 7 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 2 7/8" set at 6030' PBTD 6000' Perfs at 5943-5975'

1st plug set CIBP at 5893', 2nd plug at 2300' with 35 sx cement, 3rd plug at 1400' with 40 sx cement, 4th plug at 660' with 30 sx cement, 5th & 6th plugs - solid bridge - hulls

plug at 40' -- cement to surface with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1984

Remarks: Used Class H Cement by Western Recovered 2330' 2 7/8" casing CONSERVATION DIVISION
(if additional description is necessary, use BACK of this form.) Wichita, Kansas

observe this plugging.

Signed Paula A. Luthis (TECHNICIAN)

INVOICED
DATE 12-18-84
INV. NO. 6003