

1060425

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NE NE , SEC. 10 , T 34 S, R 26 W/K
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,673 - 0000
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name David Wilson Well # 1-10

Operator: Kaiser-Francis Oil Company

County Meade 201.50

Name & Address P. O. Box 21468

Well Total Depth 6200 feet

Tulsa, OK 74121-1468.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 860

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Gasing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 3:00 pm Day: 7 Month: December Year: 19 84

Plugging proposal received from Phil Goodwin

(company name) Midwest (phone) 316-675-8349

were: 5 1/2" set at 6200' PBDT 5730' Perfs at 4906-10'

1st plug pump 2 sx hulls and 20 sx cement to bottom

2nd plug at 1300' with 40 sx cement

3rd plug at 910' with 40 sx cement

4th plug at 400' with 20 sx cement

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthin (TECHNICIAN)
cement to surface with 10 sx cement

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:00 pm Day: 7 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 6200' PBDT 5730' Perfs at 4906-10'

1st plug pumped 2 sx hulls and 20 sx cement to bottom, 2nd plug at 1300' with 40 sx cement, 3rd plug at 910' with 40 sx cement, 4th plug at 400' with 20 sx cement, 5th

and 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED CONSERVATION COMMISSION

DEC 12 1984

Remarks: Recovered 4220' 5 1/2" casing. Used common sacked cement by Midwest Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 12-18-84

Signed Paul A. Luthin (TECHNICIAN)

INV. NO. 6006

12-7

JAN 14 1985