

1051654

5-28

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20.703 -0000
SE SE SE, SEC. 36, T 34 S, R 27 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060

330 feet from S section line
330 feet from E section line

Operator: Zinke & Trumbo, Inc.
Name:
Address 1202 E. 33rd, Ste. 100
Tulsa, OK 74105

Lease Name Wanda Smith Well # 1-36
County Meade 204.75

Well Total Depth 6300 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1525

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 12 p.m. Day: 27 Month: 5 Year: 19 93

Plugging proposal received from Kirby Lillard

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6297' w/300 sx cement, PBTD 6251', Perfs at 6034-60'

1st plug pump 20 sx cement on bottom over perfs,

2nd plug pump 50 sx cement at 1560',

3rd plug pump 40 sx cement at 500',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 28 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement,
Pumped through casing:

2nd plug pumped 50 sx cement at 1560',

3rd plug pumped 40 sx cement at 500',

4th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent's. Recovered 2980' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 6-8-93

INV. NO. 37860

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED

JUN 4 1993

CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84