

To: 1 070700
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060

Operator: Zinke & Trumbo, Inc.
Name &
Address 1202 East 33rd Street, Suite 100
Tulsa, OK 74105

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling License Number 5380

Address 2759 South Broadway, Wichita, KS 67216

Company to plug at: Hour: 3:15 p.m. Day: 20 Month: 7 Year: 19 89

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2176'
Anhydrite 1123-30'

1st plug at 1130' with 50 sx cement, 2nd plug at 590' with 40 sx cement,

3rd plug at 500' with 30 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:45 p.m. Day: 20 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1130' with 50 sx cement,

2nd plug at 590' with 40 sx cement,

3rd plug at 500' with 30 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICE (not) observe this plugging.

DATE 8-1-89

INV. NO. 25490

7-20

7-20
API NUMBER 15- 119-20,792-0000

S/2 SW, SEC. 36, T 34 S, R 27 W/E

660 feet from S section line

3960 feet from E section line

Lease Name John Chris Well # 1-36

County Meade 211.25

Well Total Depth 6500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 560

RECEIVED
STATE CORPORATION COMMISSION

7-31-89 1111 31 1989

CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Goodrow
(TECHNICIAN)