

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Clark SEC. 16 TWP. 34 RGE. 22 E/W
 Location as in quarters or footage from lines:
C/NE/NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Mustang Drilling & Exploration
 Lease Name Rankin Well No. #1 (OWWO)
 Office Address Box 1609 - Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced July 13, 1983
 Plugging completed July 19, 1983
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
 Producing formation _____ Depth to top _____ bottom T.D. 5545'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	612'	NONE
				5 1/2"	4440'	3464.59'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 4200' and five (5) sacks cement. Shot casing @ 3450'
 Pulled eighty-four (84) joints 5 1/2" casing.
 Squeezed well with three (3) sacks hulls, twenty (20) sacks gel,
 one hundred (100) sacks cement, ten (10) sacks gel, one (1) sack hulls,
 released plug and pumped one hundred fifty (150) sacks 60/40 pozmix
 cement with 2% added gel and 2% calcium chloride. Maximum pressure was
 750 psi and shut in at 500 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1983
Margaret Prosser
 Notary Public.

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION

AUG 07 1983


Wichita, Kansas

COPY

STATE OF KANSAS
CORPORATION COMMISSION

WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Clark County, Sec. 16 Twp. 34S Rge. 22 E/W
Location as "NE/CNW/SW" or footage from lines
C NE NE
Lease Owner Cameron Funk
Lease Name Rankin Well No. #1
Office Address 416 Union Center, Wichita, Kans. 6720
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed 9-6-76 19
Application for plugging filed 9-6-76 19
Application for plugging approved 9-6-76 19
Plugging commenced 9-6-76 19
Plugging completed 9-6-76 19
Reason for abandonment of well or producing formation
Commercial quantities of oil not found
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes
Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5545'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	612'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 900' w/50 sx. RECEIVED
Plug @ 600' w/35 sx. STATE CORPORATION COMMISSION
Plug @ 40' w/15 sx.
5 sx. rathole OCT 06 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains, President of Rains & Williamson Oil Co., Inc. or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of September, 1976



Juanita M. Green
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1983
CONSERVATION DIVISION
Wichita, Kansas

15-025-20117-0001

WELL LOG

COMPANY Cameron Funk

SEC. 16 T. 34S R. 22W
LOC. C NE NE

FARM Rankin NO. #1


RIG. NO. #3

TOTAL DEPTH 5545'

COMM. 8-22-76

COMP. 9-6-76

COUNTY Clark
KANSAS



CONTRACTOR Rains & Williamson Oil Co., Inc.

20" @ 92' w/300 sx.

15" 5/8" @ 612' w/300 sx. 50/50 pos.
12" 3% cc, 2% gel.
13" 5"

ELEVATION

PRODUCTION D&A

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Redbed	570
Redbed	1075
Redbed & Shale	1339
Shale	1926
Shale & Lime	2517
Lime & Shale	2816
Shale & Lime	2951
Lime & Shale	3828
Shale & Lime	3944
Lime & Shale	4110
Shale & Lime	4404
Lime & Shale	5212
Lime	5306
Lime & Shale	5545
<u>Rotary Total Depth</u>	<u>5545</u>

75. SITKA ON 183
4W.
75-4E ASHLAND.

RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1976

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1983

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the Rankin #1 well.

Wilson Rains
Wilson Rains

19 76

Subscribed and sworn to before me this 13 day of September

My Commission Expires 10-4-79

Juanita M. Green
NOTARY PUBLIC
Juanita M. Green

