

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Clark SEC. 16 TWP. 34 RGE. 22 E/W  
 Location as in quarters or footage from lines:  
C/NE/NE

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner Mustang Drilling & Exploration  
 Lease Name Rankin Well No. #1 (OWWO)  
 Office Address Box 1609 - Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced July 13, 1983  
 Plugging completed July 19, 1983  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 5545'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 612'   | NONE       |
|           |         |      |    | 5 1/2" | 4440'  | 3464.59'   |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 4200' and five (5) sacks cement. Shot casing @ 3450'  
 Pulled eighty-four (84) joints 5 1/2" casing.  
 Squeezed well with three (3) sacks hulls, twenty (20) sacks gel,  
 one hundred (100) sacks cement, ten (10) sacks gel, one (1) sack hulls,  
 released plug and pumped one hundred fifty (150) sacks 60/40 pozmix  
 cement with 2% added gel and 2% calcium chloride. Maximum pressure was  
 750 psi and shut in at 500 psi.

RECEIVED  
 STATE CORPORATION COMMISSION  
AUG 02 1983  
8-2-83

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD Box 698 - Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 83



Margaret Prosser  
 Notary Public.

My Commission expires: \_\_\_\_\_