


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

CLARK County, Sec. 15 Twp. 34S Rge. 22 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. C SE SW
Lease Owner Hummon Oil Company
Lease Name Arnold Well No. 1
Office Address 860 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed November 14, 1973
Application for plugging filed November 14, 1973
Application for plugging approved November 14, 1973
Plugging commenced November 14, 1973
Plugging completed November 14, 1973
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUSSELL BIBERSTEIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5582 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Redbed		0	721	8-5/8	721	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug - 50 sx, @600'
2nd Plug - 15 sx, @ 40'
Job completed @2:00 P.M. by Allied Cementing

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GABBERT-JONES, INC. (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James S. Sutton II
JAMES S. SUTTON II
830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 73

My commission expires May 1, 1974

Charles L. Stenning
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ARNOLD #1
C SE SW
Section 15-34S-22W
Clark County, Kansas

Commenced: October 26, 1973
Completed: November 14, 1973

OPERATOR: HUMMON OIL CO.

Depth From	To	Formation	Remarks
0	45	Sand	Ran 17 double jts - 1 single jt
45	540	Sand-redbed	used 8 5/8" csg. set @ 721' -
540	1225	Redbed	1 centralizer @ 700' & 600' & 150'
1225	1975	Shale & shells	Basket @ 150'. Cemented w/325 sks
1975	2170	Shale-lime	common, 2% Gel, 3% CC
2170	2257	Lime	P.D. 9 AM 10/27/1973. one inched
2257	2350	Shale-lime	125 sks common, 2% Gel, 3% CC on
2350	2480	Lime-shale	top of basket. Fill up to 30'.
2480	2565	Lime	
2565	2635	Shale-lime	
2635	3180	Lime	
3180	3610	Lime-shale	
3610	3666	Shale-lime	
3666	4080	Lime	
4080	4195	Shale-lime	
4195	4405	Lime-shale	
4405	4956	Lime	
4956	5000	Shale-lime	
5000	5492	Lime	
5492	5570	Shale-lime	
5570	5582	Lime	
5582	Lime		
5582		TD	DRY AND ABANDONED

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1973
CONSERVATION DIVISION
Wichita, Kansas

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SW, Section 15-34S-22W, Clark County, Kansas to the best of my knowledge and belief.

James S. Sutton, II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 23rd day of November, 1973, personally appeared James S. Sutton, II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have herunto set my hand and official seal the day and year last above written.

Marjorie Hall
Marjorie Hall, Notary Public

