

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County. Sec. 21 Twp. 34 S Rge. (E) 3 W

Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner Herndon Drilling Company
Lease Name Subera Well No. 1
Office Address 823 S. Detroit, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 8-11-55 19
Application for plugging filed 8-11-55 19
Application for plugging approved 8-11-55 19
Plugging commenced 8-11-55 19
Plugging completed 8-11-55 19
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington, Gerda Springs, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4977 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 600 feet to 40 feet for each plug set.
Hole was filled to 600 ft. with drilling mud. Plug set @ 600 ft. 15 sacks cement mixed and poured through pipe. Hole was filled to 40 ft. top plug was set and 10 sacks cement mixed and poured through pipe. Cap was welded on casing

(If additional description is necessary, use BACK of this sheet)
Herndon Drilling Company

Name of Plugging Contractor _____
Address _____

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Tom Elliott (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Tom Elliott

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1955

My commission expires Sept. 19, 1956 _____ Notary Public.

[Handwritten Signature]
Notary Public.

RECEIVED
CORPORATION COMMISSION
AUG 23 1955 8-23-55
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 21 T 34 S 3W
BOOK PAGE 42 LINE 20

WELL LOG ON SUBERA #1

Spudding date: 7/16/55
Date casing set: 7/17/55
Date rotary completed: 8/11/55
Date cable completed:

Location:
Sec. 21-34S-3W - Sumner Co., Kansas

FROM	TO	FORMATION	REMARKS
0	610	Surface Hole	Ran 19 Jts. 8-5/8" 24# Casing @ 624' Cemented w/ 350 Sx. Cement w/ 300# CC
610	1535	Shale & Lime	
1535	1755	Shale & Shells	
1755	2505	Shale & Lime	
2505	2611	Shale & Sand	
2611	2700	Shale & Lime	
2700	2770	Lime	
2770	2915	Shale & Lime	
2915	2951	Lime	
2951	3525	Shale & Lime	
3525	3630	Lime & Sand	
3630	3640	Shale & Sand	
3640	3677	Lime	
3677	4360	Lime & Shale	
4360	4756	Lime	
4756	4769	Sand & Shale	
4769	4786	Sand	
4786	4795	Shale	
4795	4893	Shale & Sand	
4893	4923	Sand	
4923	4976	Shale & Sand	
4976		Total Depth	

Plugged hole w/ 15 Sx. @ 600 Ft.
and 10 Sx. @ 40 ft.

PLUGGING
FILE SEC 21 T 34 R 3W
BOOK PAGE 142 LINE 20

Subscribed and sworn to before me this 17th
day of August, 19 55

I certify the above and foregoing to be a true and exact
copy of the original driller's log on the SUBERA #1

HERNDON DRILLING COMPANY

Patsy M. Mearns
Notary Public
My commission expires: 4/22/57

By: C. J. Mearns
Title: Assistant Secretary

CONSERVATION DIVISION
Wichita, Kansas