

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 C. Grade Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on:
API NUMBER 15-129-21070-0000

LEASE NAME Miller Q

WELL NUMBER 3

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 29 TWP. 33S RGE. 42 (E) (W)

COUNTY Morton

Date Well Completed 3-15-91

Plugging Commenced 3-15-91

Plugging Completed 3-15-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 15, 1991 (date)

by District #6 (KCC District Agent's Name).

Well was completed on:
Is ACO-1 filed? Yes if not, Is well log attached? Yes

Producing Formation None Depth to Top - Bottom - T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
<u>Morrow</u>	<u>Dry</u>	<u>-</u>	<u>-</u>	<u>8 5/8"</u>	<u>1377</u>	

APR 22 1991
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged well w/60/40 Cl.H Poz w/6% gel as follows: Plug # 4510-4180'. 75 sx; Plug #2 3100-2567' w/155 sx; plug #3 1430-1181 w/50 sx; plug #4 715-465 w/50 sx; plug #5 40-Surf. 10 sx Filled rat hole w/15 sx cmt & mouse hole w/10 sx cmt. P & A completed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Zenith Drilling Company License No.

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 20th day of March, 19 91

Cari Allen
Notary Public

My Commission Expires: 7-14-91