

To: 1 040707 10-14  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,027-00-00 86R  
SE SW NE, SEC. 22, T. 27 S, R 15 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635  
Operator: Great Bend Casing Pullers, Inc.  
Name  
Address P.O. Box 251  
Great Bend, KS 67530

2970 feet from S section line  
1650 feet from E section line  
Lease Name Covey Well # 1  
County Pratt 147.53  
Well Total Depth 4540 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 380

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 14 Month: 10 Year: 19 92

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4532', PBD 4400', Perfs at 4480-90, 4514-20, 4240-45'  
1st plug sand back to 4190' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 14 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 4 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 275 psi and shut in 125 psi. 10-16-92 OCT 16 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2611' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I ( ) ( ) observe this plugging.

DATE 10-29-92  
INV. NO. 36642

Signed Stephen L. Pfeiffer  
(TECHNICIAN)