

1 060612

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,445 - 00-00
C SW NE, SEC. 35, T 28 S, R 12 (W/X)
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Rolf Well # 1

Operator: Raymond Oil Company, Inc.
Name & Address: One Main Place, Suite 900
Wichita, KS 67202

County Pratt 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 11 Month: July Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4700' PBT 4646' Perfs at 4520-26' (4 shots per foot)

1st plug sand back to 4470' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:50 am Day: 11 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 700 psi

JUL 22 1985

7-22-85

Remarks: Recovered 2800' 5 1/2" casing. Used 60/40 Ozamita 6% gel by RI-Titan (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-85

INV. NO. 9102

observe this plugging.

Signed Paul G. Luthie (TECHNICIAN)