

1030298

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,484-00-00

C NW NE, SEC. 35, T 28 S, R 12 W/E

4620 feet N from SE Corner of MXX section line
1980 feet W from SE Corner of MXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Country _____
Lease Name Estates Well # 1

Operator: Vincent Oil Corporation

County Pratt

Name & Address 125 North Market, Suite 1110

Well Total Depth 4612 149.89 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 8:00 am Day: 5 Month: October Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 840' with 50 sx cement

2nd plug at 450' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Shumant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 am Day: 5 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement, 2nd plug at 450' with 40 sx cement

3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx

cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse

hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

10-12-84

OCT 12 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Steve Shumant (TECHNICIAN)

DATE 10-15-84

INV. NO. 4325