

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21699-00-00
Spot: NESWNE Sec/Twnshp/Rge: 35-28S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: ROLF Well Number: 1
County: PRATT Total Vertical Depth: 4545 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

Production Casing Size: 5.5 feet: 4545 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 423 WITH 150 SX CMT

147'

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/21/2003 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERIGES Phone: (620) 672-9001

Proposed Plugging Method: SAND BACK TO 4132' & 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/21/2003 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4340'. PERFS AT 4247-53 & 4533-36'. SANDED BACK TO 4132' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 500#.

RECEIVED
OCT 31 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2760' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
OCT 24 2003
KCC Dodge City

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 10-31-03
TEL. NO. 200.4060.712

Form CP-73