

1060478

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,880-0000

C S/2 N/2 NE SEC. 16, T 34 S, R 23 W/E

4290 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8802

Lease Name Eubank 16 Well # 1

Operator: Cobra Oil & Gas Corp.

County Clark 186.88

Name & Address P. O. Box 1929

Well Total Depth 5750 feet

Woodward, OK 73802

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 831

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rine Drilling Company License Number 5654

Address 300 W. Douglas, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 2 Month: February Year: 19 85

Plugging proposal received from Lloyd Hubbard

(company name) Rine (phone) 316-267-1333

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2280' with 50 sx cement

2nd plug at 1140' with 50 sx cement

3rd plug at 860' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:00 pm Day: 2 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement, 2nd plug at 1140' with 50

sx cement, 3rd plug at 860' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

FEB 07 1985

2-7-85

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

(If necessary, observe this plugging.)

DATE 2-13-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 6956

2-2

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Drilling Date: Jan 14 1985  
month day year 4:00

API Number 15- 025-20,880-0000

□ East  
C.S./2.N/2.NE Sec 16.. Twp 34.. S, Rge .. 23  West  
(location)

OPERATOR: License # 8802

Name Cobra Oil & Gas Corp.

Address P.O. Box 1929

City/State/Zip Woodward, OK 73802

Contact Person Glen A. Waugh

Phone 405.254.2027

CONTRACTOR: License # 5654

Name Rinc Drilling Co.

City/State Wichita, KS 67202 Ste. 600 300 W.

4290 Ft North from Southeast Corner of Section  
1320 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 1320 feet.

County Clark

Lease Name Eubank 16 Well # 1

Domestic well within 330 feet:  yes  no

Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment: Douglas

Oil  Swd  Infield  Mud Rotary

X Gas  Inj  Pool Ext.  Air Rotary

OWWO  Expl  Wildcat  Cable

OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

Projected Total Depth 5800 feet

Projected Formation at TD St. Gen

Projected Producing Formations

Verify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Depth to Bottom of fresh water 65 feet

Lowest usable water formation Whitehorse Formation

Depth to Bottom of usable water 200 feet

Surface pipe by Alternate: 1  2

Surface pipe to be set 800 feet

Conductor pipe if any required 70 feet

Ground surface elevation 1900 feet MSI.

This Authorization Expires 7-11-85

Approved By 1-11-85 R

1/11/85

Signature of Operator or Agent

*E. Waugh*

Title as agent

Form C-1 4/84

MHC/KOHE 1-11-85

RECEIVED  
STATE CORPORATION COMMISSION

FEB 07 1985

CONSERVATION DIVISION  
Wichita, Kansas