

To: 1121070
STATE CORPORATION COMMISSION 9-2
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 025-20,924 -0000
60' W of
C SW NE, SEC. 8, T 34 S, R 23 W/E
3300 feet from S section line
2040 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254
Operator: Midco Exploration, Inc.
Name:
Address 453 S. Webb Rd., Ste. 100
Wichita, KS 67207

Lessee Name McMillian-IDHE Well # 1A
County Clark 186.88
Well Total Depth 5750 feet
Conductor Pipe: Size 16 feet 93
Surface Casing: Size 8 5/8 feet 750

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 2 Month: 9 Year: 19 95

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling (phone) 316-624-7455

work: 4 1/2" at 5749' w/100 sx cement, Perfs at 5430-54', 5480-94'
1st plug pump 200 lbs. hulls and 20 sx cement at 5200'
2nd plug pump 50 sx cement at 800'
3rd plug pump 40 sx cement at 400'
4th plug pump 10 sx cement at 40-0'

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1995

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4 p.m. Day: 2 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement, displaced to 5200'
2nd plug pumped 50 sx cement at 780'
3rd plug pumped 30 sx cement at 400'
4th plug pumped 10 sx cement at 40'

Remarks: Used common cement by Sargent's. Recovered 4230' of 4 1/2" casing.
(If additional description is necessary, use BACX of this form.)

INVOICED
DATE OCT 10 1995
OIL NO. 43723
9-2

Signed Dustin Rankin
(TECHNICIAN)