

1 060683

API NUMBER 15- 025-20,920 - 0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW NE , SEC. 8 , T 34 S, R 23 (W) E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254
Operator: Midco Exploration, Inc.
Name & Address 200 E. First St., Suite 411
Wichita, KS 67202

Lease Name McMillion-Ihde Well # 1
County Clark 35.00
Well Total Depth 750 feet
Conductor Pipe: Size 16" feet 60
Surface Casing: Size 8 5/8" feet 0

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A
Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Co., Inc. License Number 5103
Address 422 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 8 Month: October Year: 19 85

Plugging proposal received from Don Rogers
(company name) Midco (phone) 316-267-3613

were: to fill hole with heavy mud and spot cement through drill pipe - Lost Circulation
1st plug washed with tubing to 258' and pumped 50 sx cement,
2nd plug at 160' with 10 sx cement, 3rd plug at 130' with 10 sx cement, 4th plug at 100'
with 10 sx cement, 5th plug at 70' with 20 sx cement. Lost circulation. Ran tubing
back to 100'. Got circulation with 2 sx hulls and 190 sx cement. Cement circulated

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5:20 pm Day: 8 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug washed with tubing to 258' and pumped 50 sx cement.
2nd plug at 160' with 10 sx cement, 3rd plug at 130' with 10 sx cement, 4th plug
at 100' with 10 sx cement, 5th plug at 70' with 20 sx cement. Lost circulation. Ran
tubing back to 100' and got circulation with 2 sx hulls and 190 sx cement. Cement
circulated.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1985

Remarks: Used Class H cement by Western.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE OCT 17 1985
INV. NO. 10659

Signed Paul A. Luthi (TECHNICIAN)