

To: 1 020851 4-4  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-025-20,632-0000  
C NW SE, SEC. 8, T 34 S, R 23 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5254  
Operator: Midco Exploration, Inc.  
Name & Address 453 S. Webb Rd., Ste. 100  
Wichita, KS 67207

Lease Name Fox Well # 1-8  
County Clark  
Well Total Depth 5480 17810 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 762

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 3 Month: 4 Year: 19 95

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

- were: 4 1/2" at 5479' w/1255 sx cement, PBTD 5479', Perfs at 5435-42'
- 1st plug pump 2 sx hulls and 20 sx cement at perfs,
- 2nd plug load hole with mud and pump 50 sx cement at 800',
- 3rd plug pump 40 sx cement at 400',
- 4th plug pump 10 sx cement at 40 to -4'

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 4:15 p.m. Day: 4 Month: 4 Year: 19 95

- ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs,
- 2nd plug loaded hole with mud and pumped 50 sx cement at 800',
- 3rd plug pumped 40 sx cement at 400',
- 4th plug pumped 10 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION  
APR - 7 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 4510' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** (Midco Exploration) observe this plugging.

DATE 4-13-95

INV. NO. 42566

Signed Glen R. Barlow  
(TECHNICIAN)