

1 050498

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,874 - 0000

NE NW NE , SEC. 7 , T 34 S, R 23 W/EK

4950 feet from S section line

1676 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8802

Lease Name Acres 7 Well # 1

Operator: Cobra Oil & Gas Corporation

County Clark 185.25

Name & Address P. O. Box 1929

Well Total Depth 5700 feet

Woodward, OK 73802

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 810

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rine Drilling Company License Number 5654

Address Suite 600, 300 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 2 Month: April Year: 19 85

Plugging proposal received from Don Noreill

(company name) Rine - Woodward (phone) 405-256-8763

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1410' with 50 sx cement

2nd plug at 840' with 40 sx cement

3rd plug at 420' with 30 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 pm Day: 2 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1410' with 50 sx cement, 2nd plug at 840' with 40 sx

cement, 3rd plug at 420' with 30 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(if not) observe this plugging.

DATE 4-16-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 7744

15-025-20874-0000
CORRECTION
CARD MUST BE SIGNED
3-18-85

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

Starting Date: 3 month 15 day 85 year

API Number 15-025-20,874 CORRECTION

OPERATOR: License # 8802
Name: Cobra Oil & Gas Corp.
Address: P.O. Box 1929
City/State/Zip: Woodward, OK 73802
Contact Person: Glen A. Naugh
Phone: 405-254-2027

* NE NW NE Sec 7 Twp 34 S, Rge 23
(location)
* 4950 Ft North from Southeast Corner of Section
* 1676 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5654
Name: Rine Drilling
City/State: Wichita, KS 67202

Nearest lease or unit boundary line 330 feet
County: Clark
Lease Name Acres 7 Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mod Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 65 feet
Lowest usable water formation Whitehorse Formation
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 800 feet
Conductor pipe if any required 70 feet
Ground surface elevation 1924 feet MSI
This Authorization Expires 7-2-85

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 1921 feet
Projected Formation at TD
Expected Producing Formations

Approved By: [Signature] Title: As agent
Date: 1-2-85
4750 FSL
2970 FEL

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications. kwg: NE NW
Date: 3/15/85 Signature of Operator or Agent: [Signature] Title: As agent
11005 on 3-20-85 set 810' 8578

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1985
CONSERVATION DIVISION
Wichita, Kansas