

1 070258

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,577 -0000

NE NW SE, SEC. 6, T 34 S, R 23 (W/E)

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 04824

Lease Name Cunningham Well # 1-6

Operator: Mesa Operating LTD. Partnership
Name &

County Clark 237.25

Address P.O. Box 2009, Amarillo, TX 79189

Well Total Depth 7300 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 760

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pool Company License Number 7874

Address P.O. Box 4271, Houston, TX 77210

Company to plug at: Hour: 12:15 p.m. Day: 25 Month: 11 Year: 1986

Plugging proposal received from Bill McElya

(company name) Mesa (phone) 806-378-4872

were: 4 1/2" at 5235' PBTD 5235' Perfs at 5088-92', 4712-23' Elevation 1930'GL

1st plug set CIBP at 4650' with 2 sx cement on top,

2nd plug at 2700' with 30 sx cement, 3rd plug at 940' with 20 sx cement,

4th plug at 800' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 p.m. Day: 25 Month: 11 Year: 1986

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4650' with 2 sx cement on top,

2nd plug at 940' with 20 sx cement,

12-1-85

3rd. plug at 800' with 40 sx cement,

4th plug at 40' with 10 sx cement.

DEC 1 1985

Remarks: Recovered 2735' of 4 1/2" casing. Pumped common cement by Pool Well Service.

(if additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

Signed Dan Goodrow
(TECHNICIAN)

DATE 12-3-86

INV. NO. 15462