

To: 1 060688
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,344-0000
SE, SEC. 26, T 34 S, R 24 W 1/2
1320 feet from S section line
1120 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9558
Operator: B.V.R.D. Lucher Exploration
Name & Address P.O. Box 1162
Liberal, Kansas
67901

Lease Name Randall Well # 1
County Clark 181.35
Well Total Depth 5580 feet
~~Production~~
Conductor Pipe: Size 4 1/2 feet 5580
Surface Casing: Size 8 5/8 feet 731

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargants Casing Pulling License Number 6547
Address Liberal, Kansas - 820 S Lincoln, Box 506 - Zip 67901
Company to plug at: Hour: 10:00 AM Day: 7 Month: 10 Year: 1985

Plugging proposal received from Bob Sargants
(company name) Sargants Casing Pulling (phone) 316-624-7455

were: 1st Pump 1 sbx hulls + 50 cement to bottom to cover zone @
5496' to 5532'

2nd shot off 4 1/2" & pull to 780' & pump 40 sbx cement.
3rd plug pull 4 1/2" out build bridge @ 40' & pump 15 sbx cement.
filling hole to 0'. They recovered 4025' of 4 1/2" casing.

Plugging Proposal Received by Paul A. Luttie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:00 AM Day: 15 Month: 10 Year: 1985

ACTUAL PLUGGING REPORT 1st Pumped 1 sbx hulls + 50 sbx of cement to
bottom. 2nd shot off 4 1/2" & pulled up to 780' & pumped
40 sbx cement. 3rd plug pulled 4 1/2" out of hole & built solid
bridge @ 40' & pumped 15 sbx cement down 4 1/2" that they
can in to build bridge. They used common
sacked cement.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 29 1985
INV. NO. 10749

RECEIVED
STATE CORPORATION COMMISSION
10-28-85
OCT 28 1985
DEC 13 1985

Signed Paul A. Luttie
(TECHNICIAN) P.A.L.