

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20916-00-00
Spot: E2SE Sec/Twnshp/Rge: 36-33S-29W
1320 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: CORDES Well Number: 1
County: MEADE Total Vertical Depth: 6075 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: PO BOX 116
WICHITA, KS 67201

Conductor Pipe: Size _____ feet: \$197.44
Surface Casing: Size 8.625 feet: 1510
Production: Size 4.5 feet: 5120 WITH 200 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2002 9:40 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5109'. 1ST PLUG AT 1640' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/15/2002 11:10 AM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5236'. SAND TO 5109' WITH 5 SX CMT ON TOP. 1ST PLUG PULL CASING TO 1640' & SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL CASING TO 620' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Attn: Olivia

McCoy Petroleum Corp. # 5003
needs to be invoiced. Their
address: 453 Swabb Rd, Ste 310
PO Box 78020
Wichita, KS 67278
Thanks! Michele

5-24-02
RECEIVED
MAY 24 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3060' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

INVOICED

DATE 5-28-02

INV. NO. 2002061845

Page 2/3